

AD-A104 784

PRC CONSOER TOWNSEND INC ST LOUIS MO
NATIONAL DAM SAFETY PROGRAM. WYACONDA CITY DAM (MO 10009), MISS-ETC(U)
DEC 78


F/6 13/13

DACW43-78-C-0160

NL

UNCLASSIFIED

1 of 1
AGE
103/784



END
DATE
FILMED
10-81
DTIC

LEVEL

①


MISSISSIPPI - SALT-QUINCY RIVER BASIN

AD A104784

WYACONDA CITY DAM
CLARK COUNTY, MISSOURI
MO 10009




**PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**



DTIC FILE COPY

PREPARED BY: U. S. ARMY ENGINEER DISTRICT, ST. LOUIS

FOR: STATE OF MISSOURI



DECEMBER 1978

81 9 28 212

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM	
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER	
	AD A104784		
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Wyaconda City Dam (MO 10009) Clark County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report.	
7. AUTHOR(s) Consoer, Townsend and Associates, Ltd.		6. PERFORMING ORG. REPORT NUMBER	
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) DACW43-78-C-0160	
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
12. MONITORING AGENCY NAME AND ADDRESS (if different from Controlling Office) National Dam Safety Program. Wyaconda City Dam (MO 10009), Mississippi - Salt - Quincy River Basin, Clark County, Missouri. Phase I Inspection Report.		12. REPORT DATE December 1978	
		13. NUMBER OF PAGES Approximately 90	
		15. SECURITY CLASS. (of this report) UNCLASSIFIED	
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
16. DISTRIBUTION STATEMENT Approved for release; distribution unlimited.			
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)			
18. SUPPLEMENTARY NOTES			
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams			
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property.			

DD FORM 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)



DEPARTMENT OF THE ARMY
ST. LOUIS DISTRICT, CORPS OF ENGINEERS
210 NORTH 12TH STREET
ST. LOUIS, MISSOURI 63101

IN REPLY REFER TO

SUBJECT: Wyaconda City Dam (Mo. 10009), Phase I Inspection Report

This report presents the results of field inspection and evaluation of Wyaconda City Dam (Mo. 10009). It was prepared under the National Program of Inspection of Non-Federal Dams.

SUBMITTED BY: SIGNED 29 DEC 1978
Chief, Engineering Division (Date)

APPROVED BY: SIGNED 29 DEC 1978
Colonel, CE, District Engineer (Date)

Accession For	
NTIC GRAAL	
DATE	
NAME	
ADDRESS	
PHONE	
DISTRICT	
APPROVED	
DATE	
BY	

A

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Wyaconda City Dam, Missouri Inv. No. 10009
State Located: Missouri
County Located: Clark
Stream: Unnamed Tributary of the South Wyaconda River
Date of Inspection: September 27 & 28, and October 5, 1978

Wyaconda City Dam No. Mo.10009 was inspected using the "Recommended Guidelines for Safety Inspection of Dams". These guidelines were developed by the Chief of Engineers, U.S. Army, Washington, D.C., with the help of Federal and state agencies, professional engineering organizations, and private engineers. The resulting guidelines are considered to represent a consensus of the engineering profession.

Based on the criteria in the guidelines, the dam is in the high hazard potential classification, which means that loss of life and appreciable property loss could occur in the event of failure of the dam. Three farmhouses, one state highway, and one county road would be subjected to flooding, with possible damage and/or destruction, and possible loss of life. Wyaconda City Dam is in the small size classification since it is less than 40 feet high and impounds less than 1,000 acre-feet of water.

Our inspection and evaluation indicates that the spillway of Wyaconda City Dam does not meet the criteria set forth in the guidelines for a dam having the above size and hazard potential. Wyaconda City Dam is a small size dam with a high hazard

potential required by the guidelines to pass from one-half Probable Maximum Flood to the Probable Maximum Flood without overtopping. Since there is a relatively wide valley and little development downstream of the dam, one-half of the Probable Maximum Flood is the appropriate spillway design flood. It was determined that the spillway will pass 46 percent of the Probable Maximum Flood without overtopping the dam. Also, our evaluation indicates that the spillway will not pass the 100-year flood; that is, a flood having a 1 percent chance of being equalled or exceeded during any given year..

The Probable Maximum Flood is defined as the flood discharge that may be expected from the most severe combination of critical meteorological and hydrologic conditions that are reasonably possible in the region.

Other deficiencies noted by the inspection team were a need for an annual inspection by a qualified professional engineer; lack of a maintenance schedule; embankment sloughing and surface erosion on the upstream slope; deteriorated concrete in the concrete spillway chute; a blocked spillway discharge channel with vegetative growth in this channel; cracks along the entire length of the crest of the dam on each side of the new core; a need to assure that the top of the embankment is uniform for its entire length; and a need to uncover the outlet end of the gravity drain-line. The lack of stability and seepage analysis on record is also a deficiency that should be corrected.

It is recommended that the owner take action to correct or control the deficiencies described above.



WYACONDA CITY DAN

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Wyaconda City Dam, I.D. No. 10009

TABLE OF CONTENTS

<u>Sect. No.</u>	<u>Title</u>	<u>Page</u>
SECTION 1	PROJECT INFORMATION	1
	1.1 General	1
	1.2 Description of Project	3
	1.3 Pertinent Data	7
SECTION 2	ENGINEERING DATA	10
	2.1 Design	10
	2.2 Construction	10
	2.3 Operation	10
	2.4 Evaluation	10
SECTION 3	VISUAL INSPECTION	12
	3.1 Findings	12
	3.2 Evaluation	15
SECTION 4	OPERATION PROECEDURES	17
	4.1 Procedures	17
	4.2 Maintenance of Dam	18
	4.3 Maintenance of Operating Facilities	18
	4.4 Description of Any Warning System in Effect	18
	4.5 Evaluation	18
SECTION 5	HYDRAULIC/HYDROLOGIC	19
	5.1 Evaluation of Features	19

TABLE OF CONTENTS
(Continued)

<u>Sect. No.</u>	<u>Title</u>	<u>Page</u>
SECTION 6	STRUCTURAL STABILITY	23
	6.1 Evaluation of Structural Stability	23
SECTION 7	ASSESSMENT/REMEDIAL MEASURES	26
	7.1 Dam Assessment	26
	7.2 Remedial Measures	29

LIST OF PLATES

	<u>Plate No.</u>
LOCATION MAP	1
PLAN AND ELEVATION OF DAM	2-6
GENERAL GEOLOGIC MAP	7

APPENDICES

APPENDIX A	-	PHOTOGRAPHS TAKEN DURING INSPECTION
APPENDIX B	-	HYDROLOGIC COMPUTATIONS

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

WYACONDA CITY DAM, Missouri Inv. No. 10009

SECTION 1: PROJECT INFORMATION

1.1 General

a. Authority

The Dam Inspection Act, Public Law 92-367 of August, 1972, authorizes the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspections. Inspection for the Wyaconda City Dam was carried out under Contract DACW 43-78-C-0160 to the Department of the Army, St. Louis District, Corps of Engineers, by the engineering firms of Consoer, Townsend & Associated Ltd., and Engineering Consultants, Inc. (A Joint Venture), of St. Louis, Missouri.

b. Purpose of Inspection

The visual inspection of the Wyaconda City Dam was made on September 27 & 28, and October 5, 1978. The purpose of the inspection was to make a general assessment as to the structural integrity and operational adequacy of the dam embankment and its appurtenant structures.

c. Scope of Report

This report summarizes available pertinent data relating to the project; presents a summary of visual observations made during the field inspection; presents an evaluation of hydrologic and hydraulic conditions at the site; presents an evaluation as to the structural adequacy of the various project features; and assesses the general condition of the dam with respect to safety.

It should be noted that reference in this report to left or right abutments is as viewed looking downstream. Where left abutment or left side of the dam is used in this report, this also refers to north abutment or side, and right to the south abutment or side.

d. Evaluation Criteria

Criteria used to evaluate the dam were furnished by the Department of the Army, Office of the Chief Engineers, in "Recommended Guidelines for Safety Inspection of Dams", Appendix D. These guidelines were developed with the help of several Federal agencies and many state agencies, professional engineering organizations, and private engineers.

1.2 Description of the Project

a. Description of Dam and Appurtenances

Wyaconda City Dam was originally constructed with a 10-foot wide crest, 490 feet long, at an elevation of 690.0 feet above MSL. The upstream embankment slope was 1V to 3H, and the downstream embankment slope was 1V to 2H. A 12-inch thick layer of riprap was placed for a length of 35 feet beginning at the crest and extending down the upstream slope. The embankment was originally constructed of "selected impervious fill" for the upstream two-thirds of the embankment, with "coarser material" placed in the downstream one-third of the embankment.

In 1977, the embankment section was rebuilt. A new 12-foot wide by a maximum of 32 foot deep impervious core was placed in the center of the embankment to reduce seepage through the dam. The dam crest was also raised from elevation 690.0 to elevation 691.29 by the addition of embankment material. However, the elevation of the concrete spillway wall was not raised.

The crest of the embankment is currently 12 feet wide and protected with a thin layer of gravel road base. The upstream slope has a side slope of 1V to 3H, and the riprap was covered during reconstruction. The embankment material is protected by a thin vegetative cover.

The downstream embankment slope is currently 1V to 3-4H. The slope was recently final-graded, and no vegetation was present on the slope.

Bedrock within the vicinity is composed of Mississippian age limestones. No bedrock crops out over the site. The soils of the area in which this dam is located are considered to be mixed glacial outwash modified with loessial deposits further modified by weathering.

A cut-off trench was excavated during the original construction to impervious material or bedrock along the entire length of the embankment. Side slopes of the trench are inclined at 1V to 1H, and the width of the base of the trench is 10 feet.

The spillway is an uncontrolled overflow section which is located at the right abutment. The net spillway crest length is 50 feet. The spillway crest was raised about 2.29 feet in 1977 by adding fill to the spillway approach channel. The spillway crest is at elevation 687.29 feet above MSL. The spillway consists of an earthfilled crest section, a sloping concrete chute and a concrete spillway channel. The spillway channel width narrows from 50 feet at the weir to 25 feet at the end of the channel. Chute walls on both sides of the channel are 5 feet high. There are no energy dissipators of any kind at the end of the spillway channel. The spillway channel connects with an unlined discharge channel.

A pump station vault is situated at the downstream toe of the dam, which supplies raw water through a 4-inch pipe to the treatment facilities of Wyaconda. Raw water from the reservoir reaches the pump vault through a 4-inch iron pipe outlet which passes under the base of the dam embankment.

The 4-inch outlet pipe connects at its upstream end to a length of 4-inch diameter flexible hose fitted with an intake strainer. The strainer is supported below the surface by a galvanized wire rope which is suspended from and passes over a pulley sheave to connect to a hand winch mounted on the dam embankment. The pulley sheave is supported above the reservoir surface from a timber constructed tripod structure founded on the reservoir bottom. The submergence depth of the intake strainer can be adjusted by the hoist.

In the pump vault, the 4-inch outlet pipe divides to two 4-inch branches: one branch connecting to the suction pipe of the two pumps and the other to a 4-inch drain line leading to the water course below the dam. The drain line is fitted with a gate valve and permits draining the reservoir by gravity flow.

b. Location

The Wyaconda City Dam is located on an unnamed tributary of the South Wyaconda River, Clark County, Missouri. The nearest community downstream of the dam is Medill, which is roughly 9 miles from the lake. The dam and reservoir is shown on the Wyaconda Quadrangle Sheet (7.5 minute series) in Section 33, Township 65 North, Range 9 West.

c. Size Classification

According to the "Recommended Guidelines for Safety Inspection of Dams", by the U.S. Department of the Army, Office of the Chief Engineer, the dam is classified in the dam size category as being "Small" since its storage is less than 1,000 acre-feet. The dam is also classified as "Small" in dam size category because its height is less than 40 feet. The overall size classification is, accordingly, "Small" in size.

d. Hazard Classification

The dam has been classified as having "High" hazard potential in the National Inventory of Dams, on the basis that in the event of failure of the dam or its appurtenances, excessive damage could occur to downstream property, together with the possibility of the loss of life. Our findings concur with the classification. The estimated damage zone extends 1.5 miles downstream of the dam. Within the damage zone are three farmhouses with associated farm buildings, one state highway, and one county road. The floodplain is farmed.

e. Ownership

Wyaconda City Dam is owned by the City of Wyaconda, P.O. Box 68, Wyaconda, Missouri 63474.

f. Purpose of Dam

The purpose of the dam is to impound water for use in a water supply system operated by the City of Wyaconda. The impounded water is released by means of the bottom outlet for subsequent use in the city by way of a pumping station immediately downstream from the dam.

g. Design and Construction History

Wyaconda City Dam was designed by Archer Engineering Company of Kansas City, Missouri. The dam was originally constructed in 1961.

In 1977, the embankment section was rebuilt. A new 12-foot wide by a maximum of 32-foot deep core was placed in the center of the embankment to reduce seepage through the dam. The dam crest was also raised from elevation 690.0 to elevation 691.29 by the addition of embankment material. A 4-inch diameter feeder pipe was also laid from the Wyaconda River to the lake for water supply to the reservoir.

h. Normal Operational Procedures

The dam is used to impound water for water supply for the City of Wyaconda, Missouri. The reservoir level is controlled by rainfall, runoff, evaporation and water supply requirements for the city. The reservoir is likely close to full at all times.

1.3 Pertinent Data

a. Drainage Area 200 acres

b. Discharge at Damsite All discharge at the dam-site is through an uncontrolled spillway and a water supply outlet

Estimated experienced maximum flood:	370 cfs
Estimated ungated spillway capacity at maximum pool elevation:	1,056 cfs

c. Elevation (Feet above MSL)

Top of Dam:	691.29
Spillway crest:	687.29
Minimum streambed elevation at centerline of dam:	659.29
Maximum tailwater:	Unknown

d. Reservoir	
Length of maximum pool:	1,300 feet \pm
e. Storage (Acre-Feet)	
Top of dam:	72
Spillway crest:	40
f. Reservoir Surface (Acres)	
Top of dam:	9
Spillway crest:	7
g. Dam	
Type:	Earth embankment
Length:	490 feet
Height (maximum):	32 feet
Top width:	12 feet
Side slopes:	
Upstream	1V to 3-4H
Downstream	1V to 3H
Zoning:	Upstream impervious material, impervious core placed after original construction, and downstream coarse material
Impervious core:	12 feet wide by a maximum of 32 feet deep
Cutoff:	Core trench with 10-foot bottom width and 1V to 1H side slopes
Grout curtain:	None
h. Diversion and Regulating Tunnel	
	None

i. Spillway

Type:	Uncontrolled
Length of weir:	50 feet
Crest elevation:	687.29

j. Regulating Outlets

Type:	4-inch diameter cast iron pipe
Length:	130 feet
Closure:	4-inch diameter cast iron valves
Maximum Capacity:	0.9 cfs

SECTION 2: ENGINEERING DATA

2.1 Design

Original design drawings are available for the dam and appurtenant structures. Several of these drawings are included as plates in this report. As-built drawings are currently being made for the reconstructed dam, but are not available at this time. No other design data is available.

2.2 Construction

The dam was constructed in 1961. Some reconstruction was performed in 1977, as described earlier in this report. No additional construction data is available.

2.3 Operation

No operation records for Wyaconda City Dam are available.

2.4 Evaluation

a. Availability

The only engineering data available is the original design drawings. No design computations, construction data or operation data is available.

In addition, no pertinent data was available for review on hydrology, spillway capacity, flood routing through the reservoir, outlet capacity, slope stability, seepage analysis or foundation conditions.

b. Adequacy

The design drawings are adequate to aid in evaluating the adequacy of the hydraulic and hydrologic capabilities and stability of the dam for Phase I investigations.

The lack of engineering data other than design drawings did not allow for a definitive review and evaluation. Therefore, the adequacy of this dam could not be assessed from the standpoint of reviewing and evaluating design, operation, and construction data, but is based primarily on visual inspection with the aid of the available design drawings, past performance history, and sound engineering judgment.

Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.

c. Validity

The dam and appurtenant structures appears to have been constructed in accordance with the available design drawings, however, drawings are not yet available which show the reconstruction performed in 1977.

SECTION 3: VISUAL INSPECTION

3.1 Findings

a. General

A visual inspection of Wyaconda City Dam was made on September 27 & 28, and October 5, 1978. The following persons were present during the inspection:

<u>Name</u>	<u>Affiliation</u>	<u>Discipline</u>
Yin Au-Yeung	Engineering Consultants, Inc.	Project Engineer, Hydraulics and Hydrology
David Bramwell	Engineering Consultants, Inc.	Geology
Jon Diebel	Engineering Consultants, Inc.	Soils
John Ismert	Engineering Consultants, Inc.	Mechanical
Kevin Blume	Consoer, Townsend & Assoc., Ltd.	Civil & Structural

Specific observations are discussed below.

b. Dam

The crest of the dam is protected with a thin layer of gravel base material. A crack could be seen along virtually the entire length of the crest on each side of the new core. The crack was up to 1-inch wide in some places.

The upstream embankment slope is not protected by riprap following the reconstruction. Some sloughing of the embankment material along the high water line was occurring. Also, surface erosion paths on the slope are prevalent.

Neither of these conditions has progressed to a serious degree at this time.

The downstream embankment slope had been recently regraded. This has left the slope with a smooth, well-graded finish, and clear of all vegetation.

The recent reconstruction raised the dam crest 1 to 2 feet from one abutment to the other. However, the left concrete spillway wall was not raised, forcing the crest elevation to taper to the elevation of the spillway wall.

No signs of past or present instability were seen on the embankment or in the foundation at any location. Also, no seepage was observed on the downstream embankment slope or downstream of the toe.

c. Appurtenant Structures

(1) Spillway

The original overflow weir of the spillway crest was raised about 2.29 feet in 1977. The increase in elevation was accomplished by filling up the spillway approach channel to elevation 687.29. This filled section is stable at the time of inspection, but will be eroded away when large floods pass through the section. Concrete in the spillway structure is in poor condition. Vertical cracks in the chute walls, spalling and erosion on the floor slabs, and vegetative growth between horizontal joints are apparent. However, no leakage was observed on the spillway structure at any location.

(2) Outlet Works

The hand winch and the top of the tripod structure in the reservoir were observed and seen to be in good condition. In the pump vault, the piping, pumps and valves were inspected and found to be in good operating condition. The outlet from the 4-inch gravity drain line was not located during the inspection.

d. Reservoir Area

The water level was at 687.29 feet above MSL at the time of the inspection.

Around the reservoir rim are cultivated lands and pasture with few trees. Slopes on the reservoir shore generally are flatter than 1V to 8H. No sign of erosion or slope instability were noted on the shoreline.

e. Downstream Channel

The downstream channel starts at a 90 degree turn at the end of the concrete spillway channel. The channel is well-defined, but with a much smaller cross-sectional area than the spillway channel. The cross-section of the downstream channel is a trapezoidal unlined channel with an average bottom width of 3 feet and side slopes of 1V to 1-1/2H. The channel runs parallel to the dam toe for about 300 feet, then turns 90 degrees into the natural channel.

No signs of erosion or slope sloughing in the discharge channel were observed. Vegetation was seen at the downstream end of the concrete channel and past the 90 degree turn for a distance of approximately 150 feet.

3.2 Evaluation

The visual inspection did not exhibit any items which are sufficiently significant to indicate a need for immediate remedial action.

The following items were observed which could affect the safety of the dam, or which will require maintenance within a reasonable period of time.

1. The cracks along the crest of the dam on each side of the new core.
2. The sloughing and erosion occurring on the upstream embankment slope.
3. Non-uniform elevation of the embankment crest due to the failure to raise the wall of the spillway channel.
4. Poor condition of the concrete in the spillway channel.
5. The material placed in the spillway approach channel to allow a higher water surface elevation in the reservoir.
6. The small spillway discharge channel and the 90 degree bends in the channel. Also, the channel runs parallel to the toe of the embankment for a length of 300 feet.

7. Vegetation was observed in the downstream spillway discharge channel.
8. The outlet end of the drain line appears to be buried.

SECTION 4: OPERATIONAL PROCEDURES

4.1 Procedures

Wyaconda City Dam is used to impound water from an unnamed tributary of the South Wyaconda River. The water is then used as water supply for the City of Wyaconda, Missouri.

The only operating facilities at the dam are the water supply intake and piping, which includes a pump vault downstream of the dam.

In the pump vault, the valve in each branch line of the reservoir outlet pipe is manually operated; the valve in the pump suction branch normally being kept open, and the valve in the drain branch normally closed. The drain valve would be opened to draw down the reservoir for any reason.

4.2 Maintenance of Dam

The dam is maintained by the Wyaconda Water Superintendent. Most of the problems observed at the dam involve the concrete spillway and its approach and discharge channels. These observations are discussed in various sections of this report. Maintenance of the dam and appurtenant structures appears to be generally satisfactory.

4.3 Maintenance of Operating Facilities

The operating facilities which could be observed appear to be satisfactorily maintained.

4.4 Description of Any Warning System in Effect

The inspection team is not aware of any existing warning system for this dam.

4.5 Evaluation

The operation procedures and maintenance program appears to be satisfactory at the damsite.

SECTION 5: HYDRAULIC/HYDROLOGIC

5.1 Evaluation of Features

a. Design

The watershed area of Wyaconda Lake consists of about 200 acres, of which approximately 30 percent is covered by forest. Land gradients for the watershed area average about 2 to 2.5 percent. The lake is located on an unnamed tributary of the South Wyaconda River.

Elevations within the watershed range from approximately 685 feet above MSL at the damsite to over 750 feet above MSL in the upper portion of the watershed.

A drainage map showing the watershed area is included in Appendix B.

Evaluation of the hydraulic and hydrologic features of Wyaconda City Dam was based on criteria set forth in the Corps of Engineers' Recommended Guidelines for Safety Inspection of Dams, and additional guidance provided by the St. Louis District of the Corps of Engineers. The Probable Maximum Flood (PMF) was calculated from the Probable Maximum Precipitation (PMP) using the methods outlined in the U.S. Weather Bureau Publication, Hydrometeorological Report No. 33. The probable maximum storm duration was set at 24 hours, and storm rainfall distribution was based on criteria given in EM 1110-2-1411 (Standard Project Storm). The SCS triangular hydrograph, transformed to a curvilinear hydrograph, was adopted for developing the unit hydrograph. The derived unit hydrograph is presented in Appendix B.

Initial and infiltration loss rates were applied to the PMF to obtain rainfall excesses. The rainfall excesses were then applied to the unit hydrograph to obtain the PMF hydrograph, utilizing the Corps of Engineers' computer program HEC-1, (Dam Safety Version), which was prepared specifically for dam safety analysis. The computed peak discharge of the PMF and one-half of the PMF are 4,505 cfs and 2,253 cfs, respectively.

Both the PMF and one-half of the PMF inflow hydrographs were routed through the reservoir by the Modified Puls Method, also utilizing the HEC-1 (Dam Safety Version) computer program. The peak outflow discharges for the PMF and one-half of the PMF are 3,751 cfs and 1,256 cfs, respectively. Both the PMF and one-half of the PMF, when routed through the reservoir, resulted in overtopping of the dam. The hydraulic capacity of the spillway is 1,056 cfs when water level is at the top of the dam.

The stage-outflow relation for the spillway was prepared from field notes, sketches and limited construction drawings. The reservoir stage-capacity data were based on the U.S.G.S. Wyaconda Quadrangle topographic maps (7.5 minute series, dated 1951) in combination with data given in the National Dam Safety Inventory Table. Reservoir storage capacity included surcharge levels exceeding the top of the dam, and the spillway rating curve assumed that the dam remains intact during routing. In the routing computations, the discharge through the outlet facilities was excluded due to its insignificant magnitude as compared to the spillway discharge and the PMF. The spillway rating curve and the reservoir capacity curve are also presented in Appendix B.

From the standpoint of dam safety, the hydrologic design of a dam aims at avoiding overtopping. Overtopping is especially dangerous for an earth dam because the downrush of waters over the crest will erode the dam face and, if continued long enough, will breach the dam embankment and release all the stored water suddenly into the downstream floodplain. The safe hydrologic design of a dam calls for a spillway discharge capability, in combination with an embankment crest height that can handle a very large and exceedingly rare flood without overtopping.

b. Experience Data

No records of reservoir stage or spillway discharge are maintained for this site. However, according to the owner, the maximum reservoir level was never higher than the crest of the embankment.

c. Visual Observations

The spillway structure is well-defined, but lacks proper maintenance. The filled approach channel section, without adequate protection, is vulnerable to erosion from overflows. Concrete in the spillway structure is in poor condition. There were signs of vertical cracks on the chute walls, vegetation growth in between the joints, and general spalling and erosion in concrete. Minor settlements were noted on the concrete channel floor slabs. Several reinforcing bars are exposed at floor slabs at the end of the concrete channel. The downstream channel has a cross-sectional area which is much smaller than the spillway channel, has two 90 degree bends before reaching the natural channel, and contains vegetation, restricting flow.

d. Overtopping Potential

As indicated in Section 5.1-a., both the Probable Maximum Flood and one-half of the Probable Maximum Flood, when routed through the reservoir, result in overtopping of the dam. The PMF and one-half of the PMF overtopped the dam crest by 1.34 feet and 0.13 feet, respectively. The total duration of embankment overflow is 0.58 hours during the PMF, and 0.25 hours during one-half of the PMF. The spillway of the Wyaconda City Lake Dam is capable of passing a flood equal to approximately 46 percent of the PMF just before overtopping the dam. The 100 year flood is equal to approximately 7 percent of the PMF, therefore, the spillway will pass the 100-year flood without overtopping of the dam.

Wyaconda City Lake Dam is a small size dam with a high hazard potential required by the guidelines to pass from one-half Probable Maximum Flood to the Probable Maximum Flood without overtopping. Since there is a relative wide valley and little development downstream of the dam, one-half of the Probable Maximum Flood is the appropriate spillway design flood for this dam.

The effect from rupture of the dam could extend approximately 1.5 miles downstream of the dam. There are three farmhouses, one state highway, and one county road within the four miles of the floodplain area. The floodplain is extensively farmed.

SECTION 6: STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations

There were no signs of settlement or distress observed on the embankment or foundation during the visual inspection. The upstream slope, crest, and downstream slope demonstrated some sloughing and surface erosion due to the lack of riprap, but the condition has not progressed to a serious degree at time. Cracks were observed along the crest on either side of the new core, and is a condition which should be repaired. The downstream embankment slope is in excellent condition.

The crest should have a uniform elevation due to the potential of overtopping. Overtopping on a non-uniform crest causes concentration of flows which serve to more rapidly erode the embankment materials.

There were signs of settlement on the spillway floor slabs. Moderate spalling and erosion of concrete in the entire spillway structure, especially at end sections, were apparent. Reinforcing bars are exposed in the air at the end slabs, with some holes existing in the slab at this area. Vegetation is growing between horizontal joints. All these deficiencies will, in time, adversely affect the structural stability of the spillway structure, and should be corrected. The downstream channel, if not enlarged, would be inadequate to pass the spillway discharge without encroaching into the downstream toe of the dam. The 90 degree bends would not

adequately direct the discharge flows even if the channel was of sufficient size to handle the discharge quantity.

No problems were observed with the outlet works which will jeopardize the safety of the dam. However, the drain line was apparently covered during the recent grading, and should be uncovered.

b. Design and Construction Data

No design or construction data relating to the structural stability of the dam were found. No design data relating to seepage and stability analysis are known to exist.

c. Operating Records

No operating records are available relating to the stability of the dam or appurtenant structures. Water levels have not been recorded, however, it is assumed that the dam is kept near full at all times.

d. Post Construction Changes

The following post construction changes were made which will affect the structural stability of the dam and appurtenant structures.

1. A new impervious core was constructed in the center of the embankment section in 1977 to reduce or eliminate seepage that was occurring through the dam.

2. The dam crest was raised 1.29 feet to allow additional storage capacity, and a 2.29 foot high berm of material placed above the spillway crest to permit the water to be raised without flowing over the spillway.

3. A 4-inch diameter feeder pipe was laid from Wyaconda River to the reservoir.

e. Seismic Stability

In general, projects located in Seismic Zones 0, 1 and 2 may be assumed to present no hazard from earthquake, provided the static stability conditions are satisfactory and conventional margins of safety exist. Wyaconda City Dam is located in Seismic Zone 1. A detailed seismic analysis is not felt to be necessary for this embankment.

SECTION 7: ASSESSMENT/REMEDIAL MEASURES

7.1 Dam Assessment

The assessment of the general condition of the dam is based upon available data and visual observations. Detailed investigations, testing and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

It should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection, along with data available to the inspection team.

It is also important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that an unsafe condition could be detected.

a. Safety

The spillway capacity was found to be "inadequate". The spillway of Wyaconda City Dam will pass 46 percent of the PMF.

The spillway discharge channel is also a problem which should be remedied. The channel is blocked at the downstream end of the concrete chute by the natural terrain, and must make a 90 degree turn along the downstream toe of the

embankment for a distance of 300 feet. After this 300 feet, the flow must again turn 90 degrees into the natural channel. The discharge flowing parallel to the embankment section at the toe will cause substantial undermining at the toe. Also, the 90 degree turns will restrict flow sufficiently to cause water to back up onto the downstream slope, causing saturation of the slope during flood condition.

Several other items were observed during the visual inspection which should be repaired within a reasonable period of time. These include:

1. The sloughing and erosion on the upstream embankment slope due to the lack of riprap.
2. The deteriorated condition of the concrete in the concrete spillway discharge channel.
3. The vegetation observed in the downstream spillway discharge channel.
4. The buried outlet end of the drain line.
5. The crack on the crest of the dam on either side of the new core.

b. Adequacy of Information

Information concerning operation and maintenance of the dam and appurtenant structures is somewhat lacking. It is recommended that the following programs be initiated to help alleviate this problem:

1. Annual inspection of the dam by a professional engineer experienced in the design and construction of earthen dams should be made and this inspection report made a matter of record.
2. Set up a maintenance schedule and log all visits to the dam for operation, repairs and maintenance.
3. Perform seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams".

The design drawings, together with performance history and the visual inspection findings are felt to be adequate information to support the conclusions presented in this report.

c. Urgency

The remedial measures recommended in Paragraph 7.2 should be accomplished within a reasonable period of time. Improvements to the dam crest and the spillway discharge channel are more urgent than the other remedial measures.

d. Necessity for Phase II Investigation

Based on results of the Phase I inspection, a Phase II inspection is not felt to be necessary.

7.2

Remedial Measures

a. Spillway capacity and/or height of dam should be increased to pass one-half of the PMF without overtopping.

b. The spillway discharge channel blockage should be remedied.

c. The cracking along the crest of the embankment should be corrected to prevent surface waters from entering the embankment.

d. The top of the dam should be brought to a uniform elevation to prevent concentration of flows next to the spillway from eroding the sloping top of the dam.


e. An engineer experienced in the design and construction of dams should be retained to determine the best solution to the above problems.

f. O & M Maintenance Procedures: The owner should initiate the following programs:

1. Annual inspection of the dam by a professional engineer experienced in the design and construction of earthen dams.
2. Set up a maintenance schedule and log all visits to the dam for operation, repairs and maintenance.
3. Continually watch the upstream embankment slope for embankment sloughing and surface erosion, and add riprap, as required, to protect the slope.


4. Repair the deteriorated concrete in the concrete spillway chute.
5. Remove vegetation in the present spillway discharge channel.
6. Uncover the outlet end of the drain line.
7. Seepage and stability analyses should be performed by a professional engineer experienced in the design and construction of dams.

PLATES




LOCATION MAP
WYACONDA CITY DAM
CLARK COUNTY, MISSOURI

ELEV. 0 ON DRAWINGS = ELEV. 610.0 MSL



E T ARCHER & COMPANY	
CONSULTING ENGINEERS	
SAN FRANCISCO	MISSOURI
Reservoir Site	
Plans & Details	
Water Works Improvements	
WATKINS, M. 1908.	
Sheet No. 1	Project No. 6-21



EY ARCHER & COMPANY
 CONSULTING ENGINEERS
 KANSAS CITY
 MISSOURI
 PROJECT NO. 10-10-10
 SHEET NO. 10-10-10
 DATE: 10-10-10

10-10-10
 10-10-10

C-C TYPICAL SECTION

B-B


WYACONDA - MISSOURI

SHEET NO. 1 OF

JOB NO. 1223

RATING CURVE FOR DRAIN OUTLET

BY JCE DATE 10/26/75



Determine overall flow coefficient

Pipe friction

From Hyd. Institute Tables $F \approx 6.6$ where $h_f = F \frac{v^2}{2g}$ per 100'Increase friction about 15% for ageing $F = 1.15 \times 6.6 \times \frac{330}{100} = 17.5$

$$h_f = 17.5 \frac{v^2}{2g}$$

Intake loss - assume $0.5 \frac{v^2}{2g}$ Total

$$\begin{array}{r} 17.5 \frac{v^2}{2g} \\ 0.5 \\ \hline 19.0 \frac{v^2}{2g} \end{array}$$

Friction
Entrance
Exit

WYACONDA

SHEET NO. 2 OF

JOB NO. 1223

RATING CURVE FOR DRAIN OUTLET

BY JCI

DATE 10/26/78

$$H_{\text{form}} = 19.0 \text{ ft} / 29 = \frac{19 Q^2}{A^2 (29)} = \frac{19 Q^2}{(0.87)^2 (29)}$$

$$Q = 0.87 \sqrt{\frac{29 H}{19}} = 0.16 \sqrt{H}$$

EL. FT	H. FT	Q - CFS	Q - GPM
55	5	.36	162
60	10	.51	230
65	15	.62	279
70	20	.72	324
75	25	.80	360
80	30	.88	396

Drawdown rate at design pool elevation

Surface area = 7.2 a.

time to drawdown one foot

$$= \frac{7.2 Q (43560 \text{ ft}^2/\text{a})}{.80 \text{ ft}^3/\text{s} (60)(60)(24)} = 4.5 \text{ days}$$

ENGINEERING CONSULTANTS, INC.


WYACONDA - MISSOURI


SHEET NO. 3 OF

JOB NO. 1223

RATING CURVE FOR DRAIN OUTLET

BY JCI DATE 10/26/78





Explanation

Pennsylvanian System

- P_{kc} - Kansas City group: cyclic deposits with numerous limestones.
- P_{pwm} - Pleasanton group: sandstone channel member.
- P_m - Marmaton group: cyclic deposits with limestones.
- P_{cc} - Cherokee group: cyclic deposits, predominately shale, sandstone and coal beds.

Mississippian System

- M_m - sandy, oolitic, fossiliferous, lithographic, or cherty limestones.
- M_o - cherty, crinoidal limestone, with some shale.
- M_k - intercalated limestones and shales.

Reference: Geologic Map of Missouri, 1961, Division of Geological Survey and Water Resources, State of Missouri.

APPENDIX A

PHOTOGRAPHS TAKEN DURING INSPECTION

WYACONDA CITY DAM

- Photo 1 - View across spillway and along crest taken at right abutment.
- Photo 2 - View along upstream slope of embankment taken at spillway crest.
- Photo 3 - Close-up of sloughing occurring on the upstream slope.
- Photo 4 - Close-up of surface runoff erosion occurring on upstream embankment slope.
- Photo 5 - View along downstream slope of embankment taken at left abutment.
- Photo 6 - Picture of downstream slope of embankment taken downstream of the dam.
- Photo 7 - Close-up of cracking near downstream edge of crest.
- Photo 8 - Picture of hoist arrangement for the water supply intake.
- Photo 9 - Picture of emergency spillway taken from downstream.
- Photo 10 - Picture of emergency spillway and downstream channel taken from approach channel.
- Photo 11 - Picture of spillway crest taken from right abutment.
- Photo 12 - Close-up of concrete erosion and subsequent hole near discharge end of channel.
- Photo 13 - View of downstream discharge channel for spillway. See Photo 4 for "approach channel" to downstream.
- Photo 14 - Picture of 4-inch I.D. steel pipe intake for pumped water from nearby creek.

Wyaconda City Dam



Photo 1 - View across spillway and along crest taken at right abutment.



Photo 2 - View along upstream slope of embankment taken at spillway crest.



Photo 3 - Close-up of sloughing occurring on the upstream slope.




Photo 4 - Close-up of surface runoff erosion occurring on upstream embankment slope.



Photo 5 - View along downstream slope of embankment taken at left abutment.



Photo 6 - Picture of downstream slope of embankment taken downstream of the dam.

Wyaconda City Dam



Photo 7 - Close-up of cracking near downstream edge of crest.



Photo 8 - Picture of hoist arrangement for the water supply intake.




Photo 9 - Picture of emergency spillway taken from downstream.




Photo 10 - Picture of emergency spillway and downstream channel taken from approach channel.



Photo 11 - Picture of spillway crest taken from right abutment.



Photo 12 - Close-up of concrete erosion and subsequent hole near discharge end of channel.




Photo 13 - View of downstream discharge channel for spillway.
See Photo 4 for "approach channel" to downstream.




Photo 14 - Picture of 4-inch I.D. steel pipe intake for
pumped water from nearby creek.

APPENDIX B

HYDROLOGIC COMPUTATIONS



SCALE 1 24000





CONTOUR INTERVAL 20 FEET

DATUM IS MEAN SEA LEVEL


DRAINAGE BOUNDARY - - - - -

WYACONDA CITY DAM
DRAINAGE AREA





WYACONDA CITY DAM
RESERVOIR CAPACITY CURVE



WYACONDA CITY DAM
SPILLWAY AND OVERTOP RATING CURVE

DAM SAFETY INSPECTION - MISSOURI

SHEET NO. 1 OF

WYACONDA CITY DAM

JOB NO. 1223-001-1

RESERVOIR AREA CAPACITY

BY KLB DATE 10-13-78

WYACONDA LAKE DAM

RESERVOIR AREA CAPACITY

Data are based on USGS Wyaconda Quadrangle Sheet 7.5 Minute Series) in combination with data given in the National Dam Safety Inventory Table.

ELEV (FT) M.S.L.	RESERVOIR SURFACE AREA (ACRES)	INCREMENTAL VOLUME (AC-FT)	TOTAL VOLUME (AC-FT)	REMARKS
665	0	-	0	STREAM BED AT CENTER OF DAM (LOCAL ELEV 507 MSL ELEV 665)
687.29	7.2	40.0	40.0	SPINWAY CREST (NORMAL STORAGE DATA FROM INVENTORY.)
691.29	9.0	32.4	72.4	TOP OF DAM.
700	21.1	183.8	256.2	AREA MEASURED ON U.S.G.S. QUAD MAP

DAM SAFETY INSPECTION - MISSOURI

SHEET NO. 1 OF


WYACONDA CITY DAM

JOB NO. 1223-001-1

SPILLWAY AND OVERTOP DISCHARGE CAPACITY

BY KLB

DATE 10-13-78



ELEV (FT)	H ₁ (FT)	H ₂	L ₁	L ₂	C ₁	C ₂	$Q = \sum C_i L_i H_i^{3/2}$
687' 3 1/2"	0	-	50'	-	-	-	0
688' 3 1/2"	1	-	50'	-	2.68	-	134
689' 3 1/2"	2	-	50'	-	2.64	-	379
690' 3 1/2"	3	-	50'	-	2.64	-	686
691' 3 1/2"	4	0	50'	490'	2.64	-	1056
692' 0"	4.71	0.71	50'	490'	2.64	2.68	2135
693' 0"	5.71	1.71	50'	490'	2.64	2.64	4674
694' 0"	6.71	2.71	50'	490'	2.64	2.64	8065
695' 0"	7.71	3.71	50'	490'	2.64	2.64	12070
696' 0"	8.71	4.71	50'	490'	2.64	2.64	16616
698' 0"	10.71	6.71	50'	490'	2.64	2.64	27111
700' 0"	12.71	8.71	50'	490'	2.64	2.64	39234

WYACONDA CITY DAM

JOB NO. 1223-001-1

UNIT HYDROGRAPH PARAMETERS

BY HLB DATE 10-9-78

$$1. \text{ DRAINAGE AREA} = 200 \text{ AC} = 0.31 \text{ SQ. MI.}$$

$$2. \text{ LENGTH OF STREAM IN AREA} = L = (1.9' \times 2000' / 5200') = 0.72$$

$$3. \text{ DIFFERENCE IN ELEVATION: } \Delta H$$

$$\Delta H = 750 - 685 = 65'$$

$$4. \text{ TIME OF CONCENTRATION}$$

$$T_c = \left(\frac{11.9 \times L^3}{\Delta H} \right)^{0.385} = \left(\frac{11.9 \times 0.31^3}{65} \right)^{0.385}$$

$$T_c = 0.13 \text{ HR.}$$

$$5. \text{ LAG TIME } L_t = 0.6 \times T_c$$

$$L_t = 0.6 \times 0.13 = 0.08 \text{ HR.}$$

$$6. \text{ UNIT DURATION}$$

$$D = \frac{L_t}{3} = 0.04 \text{ HR.}$$

$$\text{USE } D = 5 \text{ MIN.} = 0.083 \text{ HR}$$

(MINIMUM DURATION CRITERIA)

$$7. \text{ TIME TO PEAK}$$

$$T_p = \frac{D}{2} + 0.6 \times T_c$$

$$T_p = \frac{0.083}{2} + 0.6 \times 0.13$$

$$T_p = 0.12 \text{ HR}$$

$$8. \text{ } q_p = \frac{484 \times A}{T_p} = \frac{484 \times 0.31}{0.12} = 1250.33 \text{ CFS}$$

DAM SAFETY INSPECTION - MISSOURI

WYACONDA CITY DAM

UNIT HYDROGRAPH DERIVATION

SHEET NO. 2 OF

JOB NO. 1223-0011

BY KLB DATE 10-9-78

9) CURVILINEAR UNIT HYDROGRAPH

TIME T/TP	DISCHARGE RATIO 8/8P	UNIT HYDROGRAPH	
		TIME, T (HOURS)	DISCHARGE (CFS)
0.00	0.000	0.00	0.00
0.1	0.015	0.01	18.75
0.2	0.075	0.02	93.77
0.3	0.16	0.04	200.05
0.4	0.28	0.05	350.09
0.5	0.45	0.06	562.65
0.6	0.60	0.07	750.20
0.7	0.77	0.08	962.75
0.8	0.89	0.10	1112.79
0.9	0.97	0.11	1212.82
1.0	1.00	0.12	1250.33
1.1	0.98	0.13	1225.32
1.2	0.92	0.14	1150.30
1.3	0.84	0.16	1050.28
1.4	0.75	0.17	937.75
1.5	0.66	0.18	825.22
1.6	0.56	0.19	700.18
1.8	0.42	0.22	525.14
2.0	0.32	0.24	400.11
2.2	0.24	0.26	300.08
2.4	0.18	0.29	225.06
2.6	0.13	0.31	162.84
2.8	0.098	0.34	122.53
3.0	0.075	0.36	93.77
3.5	0.036	0.42	45.01
4.0	0.018	0.48	22.51
4.5	0.009	0.54	11.25
5.0	0.004	0.60	5.00

DAM SAFETY INSPECTION / MISSOURI

SHEET NO. 1 OF

WYACONDA CITY ~~DAM~~

JOB NO. 1223-001

ANALYSIS FOR OVERTOPPING OF DAM

BY MAS DATE 10-9-78

WYACONDA CITY LAKE DAM

1. Determine drainage area of the basin

$$D.A. = 200 \text{ Acres} = 0.31 \text{ Sq. mi}$$

2. Determine PMP Index Rainfall:


Location: $91^{\circ}54'5'' - 40^{\circ}24'$ \Rightarrow PMP for 200 Sq. mi & 24 hrs

duration = 23.94" (from Fig 1, HMR 233)

3. Determine basin rainfall in terms of percentage of PMP Index Rainfall:

Location: $91^{\circ}54'5'' - 40^{\circ}24' \Rightarrow$ Zone 7

Duration (hrs)	Percent of PMP Index Rainfall for basin area of 0.31 Sq. mi. (from Fig. 2, HMR 233) %
6	100
12	120
24	130



WYACONDA CITY DAM
5 MINUTE UNIT HYDROGRAPH

DAM SAFETY INSPECTION/MISSOURI

SHEET NO. 1 OF

WYACONDA CITY DAM

JOB NO. 1223-001

100-YEAR FLOOD BY REGRESSION EQUATION

BY MAS DATE 10-20-78

WYACONDA CITY LAKE DAM

100-YEAR FLOOD BY REGRESSION EQUATION

Regression equation for 100-year flood for
Missouri:

$$Q_{100} = 85.1 A^{0.934} S^{-0.02} S^{0.576}$$

where A = drainage area in sq. mi.

S = main channel slope ft/mi.

(Avg. slope between 0.11 and 0.85)

For Wyaconda City Lake Dam:

$$A = 200 \text{ acres} = 0.31 \text{ sq. mi.}$$

$$S = 4 \text{ ft} / 0.54 \text{ mi} = 75.93 \text{ ft/mi.}$$

$$Q_{100} = 85.1 (0.31)^{0.934} (75.93)^{-0.02} (75.93)^{0.576}$$
$$= \underline{\underline{336 \text{ cfs}}}$$

HEC1DB INPUT DATA

 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 3 AUG 78

DAM SAFETY INSPECTION - MISSOURI		HYACUNDA CITY DAM		PMF AND 50 PERCENT PMF DETERMINATION AND ROUTING	
1	A				
2	A				
3	A				
4	R	300			
5	R1	5			
6	J	1			
7	T1	1.0			
8	K	0			
9	K1				
10	P	1			
11		23.9			
12		100			
13	U	10			
14	U1	0			
15	X				
16	K	1			
17	K1				
18	V				
19	V1				
20	V4	688.29			
21	V4	698.0			
22	V5	0			
23	V527111	30230			
24	X5	0			
25	SE	605			
26	SE	605.29			
27	SE	6091.29			
28	K				

INDEX RAINFALL AND MATIUS, INPUT SCS UNIT HYDROGRAPH

1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					

ROUTE FLOOD HYDROGRAPH THROUGH HYACUNDA CITY LANT DAM

1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT 6
ROUTE HYDROGRAPH TO 6
END OF NETWORK

INFLOW PMF AND ONE-HALF PMF HYDROGRAPHS

 FLUDD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1976
 LAST MODIFICATION 3 AUG 76

RUN DATE: 78/10/26.
 TIME: 14.04.35.

DAM SAFETY INSPECTION - MISSOURI
 WYACUNDA CITY DAM
 PMF AND 50 PERCENT PMF DETERMINATION AND ROUTING

JOB SPECIFICATION									
NO	NHR	NHIN	IDAY	IMR	IMIN	MEHC	IPLY	JPRY	NSTAN
300	0	5	0	0	0	0	0	0	0
		JOPEP	NMT	LRPT	TRACE				
		5	0	0	0				

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLANE 1 NRTIO 2 INITIO 1

RTIOS= 1.00 .50

 SHH-AREA MUNDUFF COMPUTATION

 INPUT PMF INDEX RAINFALL AND RATIOS, INPUT SC5 UNIT HY
 ISTAO ICOMP IFCON ITAPE JPLY JPRY INAME ISTAGE IAUTO

HYDROGRAPH DATA									
IHYUC	IUMG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNDW	ISAME	LOCAL
1	-1	.31	0.00	.31	1.00	0.000	0	0	0

PRECIP DATA			
SPPE	PMS	RA	R24
0.00	23.90	100.00	130.00

LOSS DATA			
LRPT	STRK	RTIO	STRL
0	0.00	1.00	.85

GIVEN UNIT GRAPH, NUMGO= 10
 210.
 210.
 30.
 7.
 3.
 0.

RECESSION DATA
 STARTOR 0.00 GRESNE 0.00 RTIORE 1.00

END-OF-PERIOD FLOW									
NO.01	HR	NR	PERIOD	RAIN	EXCS	LOSS	COMP	MD.0A	MR
1	.01	.01	0.00	.01	0.	1.01	12.35	151	.20
2	.01	.01	0.00	.01	0.	1.01	12.40	152	.20
1.01	.05	.10	0.00	.01	0.	1.01	12.40	152	.20
1.01	.05	.10	0.00	.01	0.	1.01	12.40	152	.20

1.01	1.14	3	.01	0.00	.01	0.	1.01	12.45	153	.20	.19	.01	463.
1.01	1.20	4	.01	0.00	.01	0.	1.01	12.50	154	.20	.19	.01	463.
1.01	1.25	5	.01	0.00	.01	0.	1.01	12.55	155	.20	.19	.01	463.
1.01	1.30	6	.01	0.00	.01	0.	1.01	13.00	156	.20	.19	.01	463.
1.01	1.35	7	.01	0.00	.01	0.	1.01	13.05	157	.24	.23	.01	471.
1.01	1.40	8	.01	0.00	.01	0.	1.01	13.10	158	.24	.23	.01	521.
1.01	1.45	9	.01	0.00	.01	0.	1.01	13.15	159	.24	.23	.01	545.
1.01	1.50	10	.01	0.00	.01	0.	1.01	13.20	160	.24	.23	.01	554.
1.01	1.55	11	.01	0.00	.01	0.	1.01	13.25	161	.24	.23	.01	557.
1.01	1.60	12	.01	0.00	.01	0.	1.01	13.30	162	.24	.23	.01	558.
1.01	1.65	13	.01	0.00	.01	0.	1.01	13.35	163	.24	.23	.01	558.
1.01	1.70	14	.01	0.00	.01	0.	1.01	13.40	164	.24	.23	.01	558.
1.01	1.75	15	.01	0.00	.01	0.	1.01	13.45	165	.24	.23	.01	558.
1.01	1.80	16	.01	0.00	.01	0.	1.01	13.50	166	.24	.23	.01	558.
1.01	1.85	17	.01	0.00	.01	0.	1.01	13.55	167	.24	.23	.01	558.
1.01	1.90	18	.01	0.00	.01	0.	1.01	14.00	168	.24	.23	.01	558.
1.01	1.95	19	.01	0.00	.01	0.	1.01	14.05	169	.30	.29	.01	570.
1.01	2.00	20	.01	0.00	.01	0.	1.01	14.10	170	.30	.29	.01	645.
1.01	2.05	21	.01	0.00	.01	0.	1.01	14.15	171	.30	.29	.01	682.
1.01	2.10	22	.01	0.00	.01	0.	1.01	14.20	172	.30	.29	.01	682.
1.01	2.15	23	.01	0.00	.01	0.	1.01	14.25	173	.30	.29	.01	682.
1.01	2.20	24	.01	0.00	.01	0.	1.01	14.30	174	.30	.29	.01	699.
1.01	2.25	25	.01	0.00	.01	0.	1.01	14.35	175	.30	.29	.01	701.
1.01	2.30	26	.01	0.00	.01	0.	1.01	14.40	176	.30	.29	.01	701.
1.01	2.35	27	.01	0.00	.01	0.	1.01	14.45	177	.30	.29	.01	702.
1.01	2.40	28	.01	0.00	.01	0.	1.01	14.50	178	.30	.29	.01	702.
1.01	2.45	29	.01	0.00	.01	0.	1.01	14.55	179	.30	.29	.01	702.
1.01	2.50	30	.01	0.00	.01	0.	1.01	15.00	180	.30	.29	.01	702.
1.01	2.55	31	.01	0.00	.01	0.	1.01	15.05	181	.36	.36	.01	702.
1.01	2.60	32	.01	0.00	.01	0.	1.01	15.10	182	.36	.36	.01	702.
1.01	2.65	33	.01	0.00	.01	0.	1.01	15.15	183	.36	.36	.01	702.
1.01	2.70	34	.01	0.00	.01	0.	1.01	15.20	184	.54	.54	.01	702.
1.01	2.75	35	.01	0.00	.01	0.	1.01	15.25	185	.64	.63	.01	847.
1.01	2.80	36	.01	0.00	.01	0.	1.01	15.30	186	1.54	1.54	.01	1121.
1.01	2.85	37	.01	0.00	.01	0.	1.01	15.35	187	2.54	2.54	.01	1538.
1.01	2.90	38	.01	0.00	.01	0.	1.01	15.40	188	1.00	.99	.01	2072.
1.01	2.95	39	.01	0.00	.01	0.	1.01	15.45	189	.64	.63	.01	2505.
1.01	3.00	40	.01	0.00	.01	0.	1.01	15.50	190	.54	.54	.01	3221.
1.01	3.05	41	.01	0.00	.01	0.	1.01	15.55	191	.36	.36	.01	3186.
1.01	3.10	42	.01	0.00	.01	0.	1.01	16.00	192	.36	.36	.01	1996.
1.01	3.15	43	.01	0.00	.01	0.	1.01	16.05	193	.28	.27	.01	1150.
1.01	3.20	44	.01	0.00	.01	0.	1.01	16.10	194	.28	.27	.01	737.
1.01	3.25	45	.01	0.00	.01	0.	1.01	16.15	195	.28	.27	.01	707.
1.01	3.30	46	.01	0.00	.01	0.	1.01	16.20	196	.28	.27	.01	801.
1.01	3.35	47	.01	0.00	.01	0.	1.01	16.25	197	.28	.27	.01	866.
1.01	3.40	48	.01	0.00	.01	0.	1.01	16.30	198	.28	.27	.01	858.
1.01	3.45	49	.01	0.00	.01	0.	1.01	16.35	199	.28	.27	.01	658.
1.01	3.50	50	.01	0.00	.01	0.	1.01	16.40	200	.28	.27	.01	634.
1.01	3.55	51	.01	0.00	.01	0.	1.01	16.45	201	.28	.27	.01	634.
1.01	3.60	52	.01	0.00	.01	0.	1.01	16.50	202	.28	.27	.01	634.
1.01	3.65	53	.01	0.00	.01	0.	1.01	16.55	203	.28	.27	.01	634.
1.01	3.70	54	.01	0.00	.01	0.	1.01	17.00	204	.28	.27	.01	654.
1.01	3.75	55	.01	0.00	.01	0.	1.01	17.05	205	.22	.21	.01	634.
1.01	3.80	56	.01	0.00	.01	0.	1.01	17.10	206	.22	.21	.01	634.
1.01	3.85	57	.01	0.00	.01	0.	1.01	17.15	207	.22	.21	.01	634.
1.01	3.90	58	.01	0.00	.01	0.	1.01	17.20	208	.22	.21	.01	634.
1.01	3.95	59	.01	0.00	.01	0.	1.01	17.25	209	.22	.21	.01	634.
1.01	4.00	60	.01	0.00	.01	0.	1.01	17.30	210	.22	.21	.01	513.
1.01	4.05	61	.01	0.00	.01	0.	1.01	17.35	211	.22	.21	.01	511.
1.01	4.10	62	.01	0.00	.01	0.	1.01	17.40	212	.22	.21	.01	511.

1.01	5.15	63	.01	0.00	.01	0.	1.01	17.45	213	.22	.21	.01	511.
1.01	5.20	64	.01	0.00	.01	0.	1.01	17.50	214	.22	.21	.01	511.
1.01	5.25	65	.01	.01	.01	0.	1.01	17.55	215	.22	.21	.01	511.
1.01	5.30	66	.01	.01	.01	1.	1.01	18.00	216	.22	.21	.01	511.
1.01	5.35	67	.01	.01	.01	11.	1.01	18.05	217	.22	.21	.01	511.
1.01	5.40	68	.01	.01	.01	15.	1.01	18.10	218	.22	.21	.01	471.
1.01	5.45	69	.01	.01	.01	17.	1.01	18.15	219	.22	.21	.01	222.
1.01	5.50	70	.01	.01	.01	18.	1.01	18.20	220	.22	.21	.01	99.
1.01	5.55	71	.01	.01	.01	18.	1.01	18.25	221	.22	.21	.01	58.
1.01	6.00	72	.01	.01	.01	18.	1.01	18.30	222	.22	.21	.01	02.
1.01	6.05	73	.07	.06	.01	18.	1.01	18.35	223	.22	.21	.01	36.
1.01	6.10	74	.07	.06	.01	28.	1.01	18.40	224	.22	.21	.01	34.
1.01	6.15	75	.07	.06	.01	95.	1.01	18.45	225	.22	.21	.01	34.
1.01	6.20	76	.07	.06	.01	128.	1.01	18.50	226	.22	.21	.01	34.
1.01	6.25	77	.07	.06	.01	139.	1.01	18.55	227	.22	.21	.01	34.
1.01	6.30	78	.07	.06	.01	143.	1.01	19.00	228	.22	.21	.01	34.
1.01	6.35	79	.07	.06	.01	144.	1.01	19.05	229	.22	.21	.01	34.
1.01	6.40	80	.07	.06	.01	145.	1.01	19.10	230	.22	.21	.01	34.
1.01	6.45	81	.07	.06	.01	145.	1.01	19.15	231	.22	.21	.01	34.
1.01	6.50	82	.07	.06	.01	145.	1.01	19.20	232	.22	.21	.01	34.
1.01	6.55	83	.07	.06	.01	145.	1.01	19.25	233	.22	.21	.01	34.
1.01	7.00	84	.07	.06	.01	145.	1.01	19.30	234	.22	.21	.01	34.
1.01	7.05	85	.07	.06	.01	145.	1.01	19.35	235	.22	.21	.01	34.
1.01	7.10	86	.07	.06	.01	145.	1.01	19.40	236	.22	.21	.01	34.
1.01	7.15	87	.07	.06	.01	145.	1.01	19.45	237	.22	.21	.01	34.
1.01	7.20	88	.07	.06	.01	145.	1.01	19.50	238	.22	.21	.01	34.
1.01	7.25	89	.07	.06	.01	145.	1.01	19.55	239	.22	.21	.01	34.
1.01	7.30	90	.07	.06	.01	145.	1.01	20.00	240	.22	.21	.01	34.
1.01	7.35	91	.07	.06	.01	145.	1.01	20.05	241	.22	.21	.01	34.
1.01	7.40	92	.07	.06	.01	145.	1.01	20.10	242	.22	.21	.01	34.
1.01	7.45	93	.07	.06	.01	145.	1.01	20.15	243	.22	.21	.01	34.
1.01	7.50	94	.07	.06	.01	145.	1.01	20.20	244	.22	.21	.01	34.
1.01	7.55	95	.07	.06	.01	145.	1.01	20.25	245	.22	.21	.01	34.
1.01	8.00	96	.07	.06	.01	145.	1.01	20.30	246	.22	.21	.01	34.
1.01	8.05	97	.07	.06	.01	145.	1.01	20.35	247	.22	.21	.01	34.
1.01	8.10	98	.07	.06	.01	145.	1.01	20.40	248	.22	.21	.01	34.
1.01	8.15	99	.07	.06	.01	145.	1.01	20.45	249	.22	.21	.01	34.
1.01	8.20	100	.07	.06	.01	145.	1.01	20.50	250	.22	.21	.01	34.
1.01	8.25	101	.07	.06	.01	145.	1.01	21.00	251	.22	.21	.01	34.
1.01	8.30	102	.07	.06	.01	145.	1.01	21.05	252	.22	.21	.01	34.
1.01	8.35	103	.07	.06	.01	145.	1.01	21.10	253	.22	.21	.01	34.
1.01	8.40	104	.07	.06	.01	145.	1.01	21.15	254	.22	.21	.01	34.
1.01	8.45	105	.07	.06	.01	145.	1.01	21.20	255	.22	.21	.01	34.
1.01	8.50	106	.07	.06	.01	145.	1.01	21.25	256	.22	.21	.01	34.
1.01	8.55	107	.07	.06	.01	145.	1.01	21.30	257	.22	.21	.01	34.
1.01	9.00	108	.07	.06	.01	145.	1.01	21.35	258	.22	.21	.01	34.
1.01	9.05	109	.07	.06	.01	145.	1.01	21.40	259	.22	.21	.01	34.
1.01	9.10	110	.07	.06	.01	145.	1.01	21.45	260	.22	.21	.01	34.
1.01	9.15	111	.07	.06	.01	145.	1.01	21.50	261	.22	.21	.01	34.
1.01	9.20	112	.07	.06	.01	145.	1.01	21.55	262	.22	.21	.01	34.
1.01	9.25	113	.07	.06	.01	145.	1.01	22.00	263	.22	.21	.01	34.
1.01	9.30	114	.07	.06	.01	145.	1.01	22.05	264	.22	.21	.01	34.
1.01	9.35	115	.07	.06	.01	145.	1.01	22.10	265	.22	.21	.01	34.
1.01	9.40	116	.07	.06	.01	145.	1.01	22.15	266	.22	.21	.01	34.
1.01	9.45	117	.07	.06	.01	145.	1.01	22.20	267	.22	.21	.01	34.
1.01	9.50	118	.07	.06	.01	145.	1.01	22.25	268	.22	.21	.01	34.
1.01	9.55	119	.07	.06	.01	145.	1.01	22.30	269	.22	.21	.01	34.
1.01	10.00	120	.07	.06	.01	145.	1.01	22.35	270	.22	.21	.01	34.
1.01	10.05	121	.07	.06	.01	145.	1.01	22.40	271	.22	.21	.01	34.
1.01	10.10	122	.07	.06	.01	145.	1.01	22.45	272	.22	.21	.01	34.

PMF FLOOD ROUTING

MM	295.98	366.53	366.53
AC=FT	193.	234.	238.
TMNUS CU M	238.	294.	294.

HYDROGRAPH ROUTING

ROUTE FLOOD HYDROGRAPH THROUGH WYACONDA CITY L

ISTAG	ICOMP	IECON	ITYPE	JPLY	JPRY	INAME	ISTAGE	IAUTO
6	1	0	0	2	0	1	0	0

[illegible]

CLASS	CROSS	AVG	INES	ISAME	ISUP	IPAP	LSIN
0.0	0.000	0.00	1	1	0	0	0

[illegible]

1	0	0	0,000	0,000	0,000	-687,-	-1
---	---	---	-------	-------	-------	--------	----

Year	1988	1989	1990	1991	1992	1993	1994
Population (millions)	688.3	689.3	690.3	691.3	692.0	693.0	694.0
Population (millions)	700.0						

134.	373.	686.	1056.	2135.	4694.	8065.
------	------	------	-------	-------	-------	-------

3923d.

	1906	1907	1908	1909	1910	1911	1912	1913	1914	1915	1916	1917	1918	1919	1920	1921	1922	1923	1924	1925	1926	1927	1928	1929	1930	1931	1932	1933	1934	1935	1936	1937	1938	1939	1940	1941	1942	1943	1944	1945	1946	1947	1948	1949	1950	1951	1952	1953	1954	1955	1956	1957	1958	1959	1960	1961	1962	1963	1964	1965	1966	1967	1968	1969	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352	2353	2354	2355	2356	2357	2358	2
--	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	---

670.	675.	680.	685.	690.	695.	700.
------	------	------	------	------	------	------

CRCL	SPWD	CHOW	ESPM	FLEV	COOL	LAMEA	EXPL
687	0	0	0	0	0	0	0

[illegible]

TOPEL	COOD	EXPO	OAMMIO
DAM DATA			

691.3 0.0 0.0

STATION 6, PLAN 1, RATIO 1

END-OF-PERIOD HYDROGRAPH ORIGINATES

OUTFLOW

[illegible]

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
84

100

[illegible]

107.	113.	122.	129.	128.	130.
36.	17.	142.	143.	144.	146.

195.	195.	195.
195.	195.	195.
195.	195.	195.

195.	195.	195.
195.	195.	195.
195.	195.	195.
195.	195.	195.

143.	143.	143.	143.
145.	145.	145.	145.
147.	147.	147.	147.
149.	149.	149.	149.
151.	151.	151.	151.
153.	153.	153.	153.
155.	155.	155.	155.
157.	157.	157.	157.
159.	159.	159.	159.
161.	161.	161.	161.
163.	163.	163.	163.
165.	165.	165.	165.
167.	167.	167.	167.
169.	169.	169.	169.
171.	171.	171.	171.
173.	173.	173.	173.
175.	175.	175.	175.
177.	177.	177.	177.
179.	179.	179.	179.
181.	181.	181.	181.
183.	183.	183.	183.
185.	185.	185.	185.
187.	187.	187.	187.
189.	189.	189.	189.
191.	191.	191.	191.
193.	193.	193.	193.
195.	195.	195.	195.
197.	197.	197.	197.
199.	199.	199.	199.
201.	201.	201.	201.
203.	203.	203.	203.
205.	205.	205.	205.
207.	207.	207.	207.
209.	209.	209.	209.
211.	211.	211.	211.
213.	213.	213.	213.
215.	215.	215.	215.
217.	217.	217.	217.
219.	219.	219.	219.
221.	221.	221.	221.
223.	223.	223.	223.
225.	225.	225.	225.
227.	227.	227.	227.
229.	229.	229.	229.
231.	231.	231.	231.
233.	233.	233.	233.
235.	235.	235.	235.
237.	237.	237.	237.
239.	239.	239.	239.
241.	241.	241.	241.
243.	243.	243.	243.
245.	245.	245.	245.
247.	247.	247.	247.
249.	249.	249.	249.
251.	251.	251.	251.
253.	253.	253.	253.
255.	255.	255.	255.
257.	257.	257.	257.
259.	259.	259.	259.
261.	261.	261.	261.
263.	263.	263.	263.
265.	265.	265.	265.
267.	267.	267.	267.
269.	269.	269.	269.
271.	271.	271.	271.
273.	273.	273.	273.
275.	275.	275.	275.
277.	277.	277.	277.
279.	279.	279.	279.
281.	281.	281.	281.
283.	283.	283.	283.
285.	285.	285.	285.
287.	287.	287.	287.
289.	289.	289.	289.
291.	291.	291.	291.
293.	293.	293.	293.
295.	295.	295.	295.
297.	297.	297.	297.
299.	299.	299.	299.
301.	301.	301.	301.
303.	303.	303.	303.
305.	305.	305.	305.
307.	307.	307.	307.
309.	309.	309.	309.
311.	311.	311.	311.
313.	313.	313.	313.
315.	315.	315.	315.
317.	317.	317.	317.
319.	319.	319.	319.
321.	321.	321.	321.
323.	323.	323.	323.
325.	325.	325.	325.
327.	327.	327.	327.
329.	329.	329.	329.
331.	331.	331.	331.

440.	404.	426.	437.	445.	450.	455.	460.
------	------	------	------	------	------	------	------

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525

[illegible][illegible]

[illegible]

PEAK OUTFLOW IS 3751. AT TIME 15.83 HOURS

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CFS	375.1	768	240	231		69183.
CMS	100.	22	7	7		1959.
INCHES		23.03	26.83	26.83		26.83
MM		585.06	732.37	732.37		732.37
AC-FT		381	476	476		476.
THOUS CU M		470	508	508		508.

MAXIMUM STORAGE - 94.

ONE-HALF PMF FLOOD ROUTING

STATION 6, PLAN 1, RATIO 2
END-OF-PERIOD HYDROGRAPH ORDINATES[illegible]

SUMMARY OF PMF AND ONE-HALF PMF FLOOD ROUTING

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

OPERATION	STATION	AREA	PLAN	RATIO 1	RATIO 2
				1.00	.50

HYDROGRAPH AT	6	.31 (.80)	1	4505 (127.57)	2253 (63.79)
---------------	---	--------------	---	------------------	-----------------

ROUTED TO	6	.31 (.80)	1	3751 (106.22)	1256 (35.58)
-----------	---	--------------	---	------------------	-----------------

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1							
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM	
STORAGE		687.29		687.29		691.29	
OUTFLOW		45.		45.		77.	
		0.		0.		1056.	
				</			

FLOOD HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1976
LAST MODIFICATION 3 AUG 78

PERCENT OF PMF FLOOD ROUTING
EQUAL TO SPILLWAY CAPACITY

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT
ROUTE HYDROGRAPH TO
END OF NETWORK

FLUID HYDROGRAPH PACKAGE (HEC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 3 AUG 78

RUN DATE= 78/10/26
TIME= 07.46.21.

DAM SAFETY INSPECTION - MISSOURI
HYACONDA CITY DAM
PERCENT OF PMF DETERMINATION AND ROUTING

JOB SPECIFICATION									
NQ	NHR	MMIN	IDAY	IMR	IMIN	MEINC	IPLT	IPRT	INSTAN
300	0	5	0	0	0	0	0	4	0
JOPEP				LROPT		TRACE			
5				0		0			

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 1 NRTIO= 9 LRTIO= 1

RTIO= .42 .43 .44 .45 .46 .47 .48 .49 .50

SUB-AREA RUNOFF COMPUTATION

INPUT PMF INDEX RAINFALL AND RATIOS. INPUT SEC UNIT MY
ISTAG ICOMP IECON ITAPE JPLT JPRT INAME ISTAGE IAUO

HYDROGRAPH DATA

IMTDO	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	.31	0.00	.31	1.00	0.000	0	0	0

PRECIP DATA

SPFE	PM5	R6	R12	R24	R48	R72	R96
0.00	21.90	100.00	120.00	130.00	0.00	0.00	0.00

LOSS DATA

LROPT	STRKR	DLTKR	RTIUL	ERAIN	STRKS	RTIUK	STRIL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	.85	.07	0.00	0.00

RECESSION DATA

STRTOR	0.00	ORCSNA	0.00	RTIORE	1.00
--------	------	--------	------	--------	------

END-OF-PERIOD FLUX

MD,DA	HR,MN	PERIOD	RAIN	EXCS	LOSS	COMP 0	PO,DA	HR,MN	PERIOD	RAIN	EXCS	LOSS	COMP 0
-------	-------	--------	------	------	------	--------	-------	-------	--------	------	------	------	--------

SUM 31.07 20.91 2.16 60247
(789.1)(734.1)(55.2)(1961.32)

HYDROGRAPH ROUTING

ROUTE FLOOD HYDROGRAPH THROUGH WYACONDA CITY L

ISTAG	ICOMP	ICCN	LTAP	JPLT	JPR	JNAME	ISTAGE	JAUTO
0	1	0	0	0	0	1	0	0
ROUTING DATA								
QLSS	CLOSS	AVG	IRIS	IRAME	IOPT	JPMP	LSIR	
0.0	0.00	0.00	1	1	0	0	0	
NRIPS NSTOL LAG AMSKK X TSK STORA ISPRAT								
1	0	0	0.000	0.000	0.000	0.000	-687.	-1
STAGE	687.3	688.3	689.3	690.3	691.3	692.0	693.0	694.0
	698.0	700.0						695.0
FLOW	0.	134.	373.	686.	1056.	2135.	4694.	8065.
	27111.	39234.						12070.
CAPACITY	0.	8.	10.	18.	32.	61.	123.	256.
ELEVATION	665.	670.	675.	680.	685.	690.	695.	700.
CREL	SPMID	COM	EXPM	ELEV	COQL	CAMEA	EXPL	
687.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA

TOPEL	COOD	EXPD	DAMHID
691.3	0.0	0.0	0.
PEAK OUTFLOW IS	400.	AT TIME	15.92 HOURS
PEAK OUTFLOW IS	979.	AT TIME	15.92 HOURS
PEAK OUTFLOW IS	999.	AT TIME	15.92 HOURS
PEAK OUTFLOW IS	1019.	AT TIME	15.92 HOURS
PEAK OUTFLOW IS	1060.	AT TIME	15.92 HOURS
PEAK OUTFLOW IS	1070.	AT TIME	15.92 HOURS
PEAK OUTFLOW IS	1136.	AT TIME	15.92 HOURS
PEAK OUTFLOW IS	1202.	AT TIME	15.92 HOURS
PEAK OUTFLOW IS	1256.	AT TIME	15.92 HOURS

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS								
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6	RATIO 7	RATIO 8	RATIO 9
				.42	.43	.44	.45	.46	.47	.48	.49	.50
HYDROGRAPH AT	6	.31	1	1692.	1937.	1982.	2027.	2072.	2117.	2162.	2208.	2253.
	(.80)	(53.58)	59.86)	59.13)	57.41)	56.68)	59.96)	61.23)	62.51)	63.79)
ROUTED TO	6	.31	1	960.	979.	999.	1019.	1040.	1070.	1136.	1202.	1256.
	(.80)	(27.17)	27.73)	28.26)	28.86)	29.45)	30.31)	32.17)	34.02)	35.58)

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		687.29		687.29		691.29			
OUTFLOW		45.		45.		77.			
		0.		0.		1056.			
RATIO OF PHE	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.42	691.03	0.00	74.	960.	0.00	15.92	0.00		
.43	691.08	0.00	74.	979.	0.00	15.92	0.00		
.44	691.14	0.00	75.	999.	0.00	15.92	0.00		
.45	691.19	0.00	76.	1019.	0.00	15.92	0.00		
.46	691.25	0.00	76.	1040.	0.00	15.92	0.00		
.47	691.30	.01	77.	1070.	.08	15.92	0.00		
.48	691.34	.05	78.	1136.	.08	15.92	0.00		
.49	691.39	.10	78.	1202.	.08	15.92	0.00		
.50	691.42	.15	79.	1256.	.25	15.92	0.00		

DA
FILM
O —